

# REPORT OF THE (KQW)-FPT TECHNICAL WORKING GROUP

Helge Rottmann

Max-Planck-Institut für Radioastronomie

Towards high-performance mm-VLBI science operations with multi-band receivers



# FPT TECHNICAL WORKING GROUP



Workshop held in Bonn in 2022

“RADIO ASTRONOMY WITH MULTIBAND RECEIVERS AND FREQUENCY PHASE TRANSFER”

Great FPT work done by various groups already for a long time

...now FPT is turning global!

## Science Working Group

- Report available: [arXiv:2306.04516](https://arxiv.org/abs/2306.04516) (Dodson et al. 2022)

## Technical Working Group

- Currently forming
- FPT-session during GMVA Technical Group (GTG) & EVN TOG joint meeting (Sep 2025)
- Interested persons/parties **welcome to join** (Email to Helge Rottmann, MPIfR)

# FPT TECHNICAL WORKING GROUP GOAL



Operational (!) goal:

**Make KQW-FPT a standard VLBI mode for global mm-VLBI**

- Define FPT observing mode(s)
- Work towards technical readiness of array/stations/correlator

# FPT REASONING



Impact of troposphere on phase severe at high (mm/sub-mm) frequencies





Figure from Rioja, Dodson, Asaki 2022  
(<https://doi.org/10.3390/galaxies11010016>)

@230 GHz: even under **very good** conditions coherence times are < 1 min

# FPT ACTIVITIES IN THE MM/SUB-MM REGIME



In the mm/sub-mm regime FPT is the most promising approach to significantly increase the sensitivity (order of magnitude)



# FPT ACTIVITIES IN THE MM/SUB-MM REGIME



## EHT

230 GHz

Up to 11 stations



## ngEHT (planned)

86, 230, 345 GHz FPT

Telescopes need to be equipped with multi-band receivers

## FPT activities

- Technical working group coordinated by S. Issaoun / D. Pesce (CfA)
- First tests carried out (86 => 230 GHz)





# FPT ACTIVITIES IN THE MM/SUB-MM REGIME



## GMVA



**86 GHz & 43 GHz**

Up to 26 stations

Subset of telescopes are or will be equipped with KQW triple band receivers


### FPT activities

- Coordinated by MPIfR
- Technical Working Group forming



Towards high-performance mm-VLBI science operations with multi-band receivers

# KQW-RECEIVER ROADMAP



## KQW Receiver

- Operational
- Commissioning
- Under construction
- Planned

## GMVA

- Member
- Associated



# KQW(D)-RECEIVER TIMELINE



**Table 1. Status of existing, planned, and potential future multiband SOP receivers**

Antenna	Receiver Band				
	22 GHz	43 GHz	86 GHz	129 GHz	230 GHz
KVN: Yonsei	in operation	in operation	in operation	in operation	<i>planned</i>
KVN: Ulsan	in operation	in operation	in operation	in operation	
KVN: Tamna	in operation	in operation	in operation	in operation	
KVN: Pyeongchang	<i>in 2024/Q3</i>	<i>in 2024/Q3</i>	<i>in 2024/Q3</i>	<i>in 2024/Q3</i>	<i>in 2024/Q3</i>
Sejong	in operation	in operation	<i>possible</i>		
Yebes	in operation	in operation	in operation		
ATCA *	in operation	in operation	in operation		
Noto	<i>in 2023/Q4</i>	<i>in 2023/Q4</i>	<i>in 2023/Q4</i>		
SRT	<i>in 2023/Q4</i>	<i>in 2023/Q4</i>	<i>in 2023/Q4</i>		
Medicina	<i>in 2024/Q2</i>	<i>in 2024/Q2</i>	<i>in 2024/Q2</i>		
Effelsberg	<i>in 2024/Q2</i>	<i>in 2024/Q2</i>	<i>in 2024/Q2</i>		
Metsähovi	<i>In 2026/Q1</i>	<i>In 2026/Q1</i>	<i>In 2026/Q1</i>		
Onsala	<i>design</i>	<i>design</i>	<i>design</i>		
Tianma	<i>planned</i>	<i>planned</i>	<i>planned</i>		
Nobeyama	<i>under tests</i>	<i>under tests</i>	<i>under tests</i>		
Mopra	<i>planned</i>	<i>planned</i>	<i>planned</i>		
Pico Veleta	<i>possible</i>	<i>possible</i>	<i>under tests</i>	<i>possible</i>	<i>under tests</i>
NOEMA	<i>possible</i>	<i>possible</i>	<i>possible</i>	<i>possible</i>	<i>possible</i>
APEX	<i>possible</i>	<i>possible</i>	<i>possible</i>	<i>possible</i>	<i>possible</i>
Zelenchukskaya	<i>possible</i>	<i>possible</i>	<i>possible</i>		
Badary	<i>possible</i>	<i>possible</i>	<i>possible</i>		

\* - limited frequency range, operating in the paired-antenna mode, using single-band receivers.

- ← Partially commissioned in 2025
- ← Commissioning expected to start in summer 2026
- ← Partially commissioned
- ← Commissioning starts in fall 2025
- ← Under construction; expected summer 2026
- ← Under construction; expected 2026
- ← Funding secured in Oct 2025

Table from Dodson et al. 2022 ([arXiv:2306.04516](https://arxiv.org/abs/2306.04516))

# KQW-FPT TIMELINE

---



Within 2026:

**Likely up to 10 stations** with working KQW systems

Europe: up to 5 stations (**currently 1**)

Asia: up to 5 stations (currently 3)

## Test observations in 2026

- **Goal:** accommodate FPT tests within GMVA Session II (c262) in Sep. 2026
- Commissioning of European stations until summer 2026 crucial
- Feasibility to be continuously evaluated based on commission progress

# TECHNICAL TASKS



## Observing Strategy

- Ideally: Exact integer frequency multiples, e.g. 22/44/88 GHz
- Tuning capabilities at stations must be respected
- Avoid water vapor line at 22.24 GHz
- Band widths & polarizations

## Station Technical Readiness

- Backends must support number of used IFs (e.g. KQW, dual pol = 6 IFs)
- Recording speed must match the produced data rates (e.g. 12 Gbps)
- Sufficient recording volume must be available (local storage or disk modules)


## Correlator Technical Readiness

- Compute resources match increase in processing volume
- Available man power matches increase in correlation volume
- Sufficient storage volume must be available

# PROPOSED OBSERVING STRATEGY



KQW dual-pol @ 12 Gbps



- Recording data rate = 12 Gbps
- Data volume = 130 Tbyte / 24 hrs / station
- Backend IFs = 6

# NEXT STEPS

---



## Formalize Technical Working Group

- Mailing list
- Regular meetings

## Assess technical capabilities of array, stations & correlator, e.g.

- Frequency capabilities (RX, tuning, band widths)
- Backend capabilities
- Recorder capabilities
- Storage capabilities (stations, correlator)
- Commissioning status of KQW receivers
- ....



# NEXT STEPS

---



Define standard mode for KQW-FPT observations with the GMVA

- Based on technical capabilities of array/stations/correlator
- Identify required technical upgrades at stations (e.g. backends, recorders)
- Coordinate upgrade procedure

Organize test observations

- Based on technical readiness of the array
- Define scheduling strategy
- Provide feedback loop between technical / analyst people

# ADDITIONAL CHALLENGES

---



## Source Structure

- Strategies for source structure removal from phase calibration
- Large overlap with geodetic VLBI community

## Proposal & Review

- e.g. NRAO not involved in FPT observations
- KQW spans frequency boundaries of existing arrays

## Scheduling

- Sub-Arraying / Only subset of GMVA telescopes support FPT (separate FPT session ?)
- Find suitable sources and observing times with common visibility between Asia and Europe

...probably much more to think about



Thank  
you !